

| Vendor                           | Scope Description                       | Quantity | Unit | Unit Price | Total Price |
|----------------------------------|-----------------------------------------|----------|------|------------|-------------|
| Simmons Construction             | Mobilization                            |          | 1 LS | —          | \$1,500.00  |
| Simmons Construction             | Full Rehab – Mill 2", pave 2", restripe | 7,036 SF | SF   | \$5.11     | \$35,953.96 |
| Simmons Construction             | Partial Rehab – Mill 2", pave 2"        | 1,210 SF | SF   | \$15.21    | \$18,404.10 |
| Paragon Sitework (Full Lot)      | Mill 2", pave 2", restripe              | 830 SY   | SY   | —          | \$36,190.30 |
| Paragon Sitework (Partial Patch) | Sawcut/remove 2", pave 2"               | 135 SY   | SY   | —          | \$14,140.00 |
| Coastal Asphalt (Partial Repair) | Mill/remove 2", replace                 | 1,210 SF | SF   | \$15.35    | \$18,573.50 |
| Coastal Asphalt (Full Lot)       | Mill & overlay 2"                       | 900 SY   | SY   | \$31.50    | \$28,350.00 |
| Coastal Asphalt                  | Pavement markings                       |          | 1 LS | \$2,500.00 | \$2,500.00  |